

PLANT SCHEDULE - STAGE 1A

KEY	BOTANICAL NAME	COMMON NAME	MATURE HEIGHT & SPREAD (m)	INSTALLED POT SIZE	INSTALLED HEIGHT (min)	QTY
Up	Ulmus parvifolia 'Todd'	Chinese Elm	10 x 9	45Lt/35mm cal.	2.0m	13
Em	Eucalyptus mannifera 'Little Spotty'	Dwarf Brittle Gum	8 x 6	45Lt/30mm cal.	2.0m	10
Pc	Pyrus calleryana 'Bradford'	Ornamental Pear	12 x 9	45Lt/35mm cal.	2.0m	5
Cm	Corymbia maculata	Spotted Gum	20 x 12	45Lt/30mm cal.	2.4m	7

DRAWING ACCURACY NOTE


This drawing has been prepared upon Engineering drawings which may have been superseded. The Contractor is advised to consult with other trades and the Construction Manager should any discrepancies become apparent prior to & during construction.

SERVICES NOTES

Location of all services are to be confirmed on site. Contact 'Dial Before You Dig' & Refer Civil drawings for services key and further

SETOUT NOTE

Setout to be approved on site by the Superintendent prior to commencement of construction works.





== STAGE BOUNDARY

TREE SETOUT NOTES

services, crossovers and lighting.

2. Final setout of trees to be confirmed on site by the Superintendent


1. Proposed trees may require removal / relocation to allow for

3. Trees are not to be placed directly above services (including gas and water)

4. Trees are to be planted with formed watering basins and mulched.

CULTIVATION NOTE

Cultivation to be approved by the Superintendent prior to Civil placing topsoil.



All advanced trees to be healthy well-grown specimens free of pests and diseases. Water trees prior to planting.

Stake all trees with 3 No. 50x50x2100mm chisel-pointed hardwood stakes driven 300mm into the ground. Tie trees immediately after planting with flexible rubber or canvas ties in 'figure 8' configuration. Secure ties to stakes by wrapping around stakes and nailing with

NOTE- Stakes are to be painted black.

Place top of rootball flush with finished level of planting hole. Gently tease outer root system avoiding major disturbance of plant. Form a watering saucer around immediate crown of plant to hold at least 35 litres of water. Spread a 100mm layer of approved mulch to saucer. Mulch to be kept 100mm away from trunk.

Apply approved fertiliser at rates as per specification. Avoid direct root contact with

Over excavate hole by at least twice the width of the rootball. Ensure sides of hole are roughened. Depth of planting hole no deeper than the height of the root ball. Break / crack soil at base of hole. Backfill hole with approved

TYPICAL TREE PLANTING DETAIL Scale: 1:20 @ A1

CITY OF MELTON **ENGINEERING PLANS** (LANDSCAPE) **APPROVED** W/19/1 4/2/2020 CITY DESIGN

LIST OF REVISIONS

- Updated base plans (electrical & civil)
- Show trees for future Taylors Road reserve Add annotations to Detail 02
- Show reduced offset service zone
- Adjust tree locations


REV B

- Intersection base plan included
- Turf grassing added
- Surface treatment to substation noted Street trees to south side of Lily Way included
- within scope

Plant schedule

NOT FOR CONSTRUCTION

FOR TOWN PLANNING PURPOSES ONLY



BOTANIA RESIDENTIAL SUBDIVISION

1152-1174 TAYLORS ROAD & 451-471 BEATTYS ROAD, PLUMPTON

STAGE 1A LANDSCAPE STREETSCAPE PLAN & DETAILS



