

### **LEGEND**

PROPOSED TREES Refer Plant Schedule, specification & details on L01

GARDEN BED PLANTING

Refer plant schedule, specification and Details 03 &

GARDEN BED PLANTING - SACRIFICIAL Planting to be removed and reinstated with grass at the removal of the temporary retarding basin unless otherwise agreed to be retained with council

PLASTIC EDGING

Refer Detail 05/L02 and specification. Edging to be removed with removal of sacrificial planting

GRASSING Refer Specification

**GRASSING - INSTANT TURF** Refer Specification and Detail 06/L02

**STAGE BOUNDARY** 

### **CULTIVATION NOTE**

Cultivation to be approved by the Superintendent prior to Civil placing

## DRAWING ACCURACY

This drawing has been prepared upon Engineering drawings which may have been superseded. The Contractor is advised to consult with other trades and the Construction Manager should any discrepancies become apparent prior to & during construction.

## **SERVICES NOTES**

Location of all services are to be confirmed on site. Contact 'Dial Before You Dig' & Refer Civil drawings for services key and further

#### SETOUT NOTE

Setout to be approved on site by the Superintendent prior to commencement of construction works.

### TREE SETOUT GUIDELINES

1. Street trees are to be positioned on site generally in accordance with the following offsets, where possible: Pedestrian pathways Driveways Side entry pits or standard pits Service crossings Fire plugs Domestic service tapping points 2.5m Stormwater outlet points Intersections 10m (or following splay of the Lot)

Electrical infrastructure 2. Proposed trees may require removal / relocation to allow for

3. Nature strip trees are to be located mid-way between front of path and back of kerb (except where indicated otherwise on the drawing). Where a footpath is not provided, trees are to be placed

4. Trees are not to be placed directly above services.

as though a footpath existed.

5. Final setout of trees to be confirmed on site by the Superintendent & Council prior to installation.

# NOT FOR CONSTRUCTION FOR TOWN PLANNING PURPOSES ONLY

-	12/10/2021	Council submission
P5	07/10/2021	For client review - new garden beds
P4	01/10/2021	Tree coordination with PowerPlant
P3	22/09/2021	For client review


GROWLAND PTY LTD

BOTANIA RESIDENTIAL SUBDIVISION 1152-1174 TAYLORS ROAD & 451-471 BEATTYS ROAD, PLUMPTION


STAGE 4A LANDSCAPE STREETSCAPE PLAN

CITY OF MELTON			
ENGINEERING I	PLANS		
(LANDSCAPE)			
/ APPROVED			
E WIGHT	13/10/2021		
CIT¥ DESIGN	DATE		

NC/AP



#### PASSIVE STREET TREE IRRIGATION GRAVEL TRENCH (KERB INLET DIVERSION)



BACK OF KERB (mm) ≤ 2.50 2.80 800 1000 ≥ 4.35

**GENERAL NOTES** 

AT HIGHLY CONSTRAINED SITES, GRAVEL TRENCHES CAN BE MODIFIED IN THE FOLLOWING WAYS:

- REDUCED OFFSET OF 0.75m FROM TREE CENTRELINE - DIMENSION 1.0m LONG x 0.6m WIDE x 0.75m DEEP - NATURESTRIP  $\leq$  2.5m DIMENSION CAN BE 1.5m LONG x 0.4m WIDE x 0.75m DEEP

FOR PASSIVE STREET TREE IRRIGATION DETAIL REFER TO MELTON CITY COUNCIL STANDARD DRAWING. PASSIVE STREET TREE IRRIGATION GRAVEL TRENCH (KERB INLET DIVERSION) PASSIVE IRRIGATION PIPES AND FITTINGS TO BE Ø90mm PVC SEWER CLASS

ALL PVC JOINTS TO BE SEALED WITH SOLVENT CEMENT

ALL GRASSED AREAS TO BE TOP DRESSED WITH 100mm TOPSOIL AND SEEDED AS SPECIFIED

(KERB INLET DIVERSION)

**CROSS SECTION A-A** 

N.T.S.

Scale: NTS


COUNCIL STANDARD PASSIVE STREET TREE IRRIGATION GRAVEL TRENCH DETAIL (BY CIVIL)

All advanced trees to be healthy well-grown specimens free of pests and diseases. Water trees prior to planting. Stake all trees with 3 No. 50x50x2100mm chisel-pointed hardwood stakes driven 300mm into the ground. Tie trees immediately after planting with flexible rubber or canvas ties in 'figure 8' \_⊮Mulch 750 mi


configuration. Secure ties to stakes by wrapping around stakes and nailing with galvanised nails. NOTE- Stakes are to be painted black. Place top of rootball flush with finished level of planting hole. Gently tease outer root system avoiding major disturbance of plant. Form a watering saucer around immediate crown of plant to hold at least 35 litres of water. Spread a 100mm layer of approved mulch to saucer. Mulch to be kept 100mm away from trunk. Apply approved fertiliser at rates as per specification. Avoid direct root contact with fertiliser. Over excavate hole by at least twice the width of the rootball. Ensure sides of hole are roughened. Depth of planting hole no deeper than the height of the root ball. Break / crack soil at base of hole. Backfill hole with approved soil.

TYPICAL TREE PLANTING DETAIL


Scale: 1:20 @ A1



TYPICAL TUBESTOCK PLANTING DETAIL Scale: 1:10 @ A1




TYPICAL TURF DETAIL



TYPICAL SHRUB PLANTING DETAIL

Scale: 1:10 @ A1




CITY OF MELTON ENGINEERING PLANS (LANDSCAPE) **APPROVED** 13/10/2021 CITY DESIGN

PLASTIC WOOD COMPOSITE EDGE DETAIL

Scale: 1:10 @ A1

NOT FOR CONSTRUCTION FOR TOWN PLANNING PURPOSES ONLY



GROWLAND PTY LTD

BOTANIA RESIDENTIAL SUBDIVISION 1152-1174 TAYLORS ROAD & 451-471 BEATTYS ROAD, PLUMPTION

STAGE 4A LANDSCAPE DETAILS



Scale: 1:10 @ A1