

#### PLANT SCHEDULE

KEY	BOTANICAL NAME	COMMON NAME	MATURE HEIGHT & SPREAD (m)	INSTALLED POT SIZE	INSTALLED HEIGHT (min)	QTY
Up	<i>Ulmus parvifolia</i> 'Todd'	Chinese Elm	10 x 9	45Lt/35mm cal.	2.0m	14
Ce	<i>Corymbia eximia</i> 'Nana'	Dwarf Yellow Bloodwood	10 x 7	45Lt/30mm cal.	2.0m	18
Em	Eucalyptus mannifera 'Little Spotty'	Dwarf Brittle Gum	8 x 6	45Lt/30mm cal.	2.0m	13

**REVISION HISTORY: REV A** 

Trees to Marigold street turned on. Missing on drawing.

REV B

Lot 540 - Tree and passive irrigation (PI) added Lot 545 - PI location updated Lot 511 - PI removed as per Powerplant request Lot 507 - Tree and corresponding PI shifted

Future potential street trees on Marigold Drive at

front of Lot 609 & 610 shown

**REV C** 

## LEGEND



#### PROPOSED TREES

Refer Plant Schedule, specification & Detail 01 & 02. PROPOSED TREE WITH REDUCED OFFSET TO

Note: zone indicated represents 2.5m radius from the

#### SERVICES Modified passive irrigation required. Tree installation to be confirmed on site with Council representative.



PROPOSED TREES TO FUTURE STAGES To be submitted with Stage 6A plans

GRASSING Refer Specification

centre of the tree

**— — — — STAGE BOUNDARY** 

## CULTIVATION NOTE

Cultivation to be approved by the Superintendent prior to Civil placing topsoil.

## DRAWING ACCURACY

This drawing has been prepared upon Engineering drawings which may have been superseded. The Contractor is advised to consult with other trades and the Construction Manager should any discrepancies become apparent prior to & during construction.

### SERVICES NOTES

Location of all services are to be confirmed on site. Contact 'Dial Before You Dig' & Refer Civil drawings for services key and further detail.

## SETOUT NOTE

Setout to be approved on site by the Superintendent prior to commencement of construction works.

#### TREE SETOUT GUIDELINES

1. Street trees are to be positioned on site <u>generally</u> in					
accordance with the following offsets, where possible:					
Pedestrian pathways	1.2m				
Driveways	2.5m				
Side entry pits or standard pits	2m				
Service crossings	2.5m				
Fire plugs	2.5m				
Domestic service tapping points	2.5m				
Stormwater outlet points	2.5m				
Intersections	10m (or following				
	splay of the Lot)				
Electrical infrastructure	2.5				
Light poles	3m				
<u> </u>					

2. Proposed trees may require removal / relocation to allow for services, crossovers and lighting.

3. Nature strip trees are to be located mid-way between front of path and back of kerb (except where indicated otherwise on the drawing). Where a footpath is not provided, trees are to be placed as though a footpath existed.

4. Trees are not to be placed directly above services.

5. Final setout of trees to be confirmed on site by the Superintendent & Council prior to installation.


## NOT FOR CONSTRUCTION FOR TOWN PLANNING PURPOSES ONLY

С	22.03.2022	Council Resubmission	
В	02.03.2022	Council Resubmission	
A	22.02.2022	Council Resubmission	
-	07.02.2022	Council Submission	
P5	03.02.2022	Design Review	
P4	12.01.2022	Design Review	
Р3	22.12.2021	For Coordination of tree placement	
P2	08.12.2021	For Coordination of services	
P1	19.11.2021	For Coordination of services	
Rev	Date	Description	


GROWLAND PTY LTD

#### **BOTANIA RESIDENTIAL SUBDIVISION** 1152-1174 TAYLORS ROAD & 451-471 BEATTYS ROAD, PLUMPTION

#### STAGE 5A LANDSCAPE STREETSCAPE PLAN








**KEY PLAN** (INDICATIVE STAGING PLAN) NOT TO SCALE

**CITY OF MELTON** ENGINEERING PLANS Wrakt 22 Mar 2022




# COUNCIL STANDARD PASSIVE STREET TREE IRRIGATION GRAVEL TRENCH DETAIL (BY CIVIL)

Scale: NTS

01

-



All advanced trees to be healthy well-grown specimens free of pests and diseases. Water trees prior to planting.

Stake all trees with 3 No. 50x50x2100mm chisel-pointed hardwood stakes driven 300mm into the ground. Tie trees immediately after planting with flexible rubber or canvas ties in 'figure 8' configuration. Secure ties to stakes by wrapping around stakes and nailing with galvanised nails. NOTE- Stakes are to be painted black.

Place top of rootball flush with finished level of planting hole. Gently tease outer root system avoiding major disturbance of plant. Form a watering saucer around immediate crown of plant to hold at least 35 litres of water. Spread a 100mm layer of approved mulch to saucer. Mulch to be kept 100mm away from trunk.

Apply approved fertiliser at rates as per specification. Avoid direct root contact with fertiliser.

Over excavate hole by at least twice the width of the rootball. Ensure sides of hole are roughened. Depth of planting hole no deeper than the height of the root ball. Break / crack soil at base of hole. Backfill hole with approved soil.





#### **NOT FOR CONSTRUCTION** FOR TOWN PLANNING PURPOSES ONLY

-	22.03.2022	Council Submission - Reissue only, no revision	
-	02.03.2022	Council Submission - Reissue only, no revision	
-	22.02.2022	Council Submission	
-	07.02.2022	Council Submission	
P1	12.01.2022	Design Review	
Rev	Date	Description	

GROWLAND PTY LTD

#### BOTANIA RESIDENTIAL SUBDIVISION 1152-1174 TAYLORS ROAD & 451-471 BEATTYS ROAD, PLUMPTION

STAGE 5A LANDSCAPE DETAILS

